Operator	Building transformation	Main controls
Densification	Increase height while retaining the footprint	Maximum height gain of 30%, subject to height limits and remaining unit capacity
Ground release	Reduce the footprint and attempt to compensate for floor-area loss by increasing height	Maximum footprint reduction of 25%; compensation is subject to height limits
Volume splitting	Introduce a central gap and attempt height compensation	Applies to buildings with footprints of at least 300 m^2; gap size varies with intensity
Height redistribution	Reduce height near housing and heritage buildings and transfer height to more distant buildings within the same unit	Resulting buildings must satisfy height and unit-capacity limits
Public-asset setback	Reduce the street-facing footprint of public assets while retaining height	Maximum setback of 4 m
Courtyard access improvement	Cut a candidate passage from the street-facing edge towards a courtyard while retaining height	Maximum passage width of 3 m